

**Addendum No. 1**  
November 18, 2025

**TUL Wayfinding Implementation Phase III Post Security Sign Project**  
Tulsa Airports Improvement Trust Project No. 70731

This addendum is hereby made a part of the project documents to the same extent as though it were originally included therein. The following changes, modifications, corrections, clarifications, additions, and/or deletions as set forth herein shall apply to the above-referenced proposal package and shall be made apart hereof and be subject to all of the requirements as though originally specified and/or shown. **The bidder shall acknowledge receipt of this addendum in the appropriate blank of the bid form.**

This Addendum is issued to provide the following information/clarification:

Attachments:

1. Exhibit A – Bid Form / Bid Tabulation Rev. 1
2. Bidder Questions

**Exhibit A - Bid Form / Bid Tabulation Rev. 1**

**ITEM 1**

This addendum provides the final Exhibit A - Bid Form / Bid Tabulation Rev. 1 in Attachment 1.

**Bidder Questions**

**ITEM 1**

This addendum provides submitted Bidders Questions and answers to the Bidders Questions in Attachment 2.

**End of Addendum No. 1**

**ATTACHMENT 1****Tulsa International Airport****Project # 70731 – Wayfinding Implementation, Post Security Signage Project**Bid Form **Rev.1** Date: **November 18, 2025**

Bid Submitted by:

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

<b>SignType</b>	<b>Description</b>	<b>Qty</b>	<b>Unit Cost</b>	<b>Extended Cost</b>
CB.RG.A2	Various Vinyl Graphics	11		
DR.A1	Suspended Overhead Directional	2		
DR.A1W	Wiring from Nearest Suitable Fixture (in Feet)	10		
DR.B1	Wall Mounted Overhead Directional, Embedded Location	2		
DR.B1W	Wiring from Nearest Suitable Fixture (in Feet)	10		
DR.C2	Wall Mounted Overhead Directional, Unique Size	5		
DR.C2W	Wiring from Nearest Suitable Fixture (in Feet)	10		
DR.D1	Dimensional Letters	23		
ID.B1	Small Identification Flag	16		
ID.B1W	Wiring from Nearest Suitable Fixture (in Feet)	10		
ID.B3	Double Sided Flag Sign	37		
ID.B3W	Wiring from Nearest Suitable Fixture (in Feet)	10		
ID.B3.1	Double Sided Flag Sign, 34" wide	34		
ID.B3.1W	Wiring from Nearest Suitable Fixture (in Feet)	10		
ID.E1	Restroom Plaque	10		
ID.E2	Room ID Plaque	12		
ID.E3	Emergency Services Plaque	10		
ID.E4	Elevator Code Plaque	3		
	<b>APPROVED SHOP DRAWINGS</b>	1		
	<b>APPROVED MOCK-UP SIGNS</b>	1		
	<b>TOTAL BASE BID</b>			

# ATTACHMENT 2

TULSA AIRPORT IMPROVEMENT TRUST  
70731 Wayfinding Implementation Phase III Post Security Signs Project- BIDDER QUESTION LOG  
November 18, 2025

NO.	BIDDER QUESTION	Quantity of 10 feet per Sign
1	A. There are descriptions on Exhibit A asking "Wiring from nearest suitable fixture in feet". Is this just electrical wiring? B. Since type DR.A1 signs and B1 have monitors, does this include Data cable as well?	A. Please include cost for material and labor Installation of DR.A1W and DR.B1W Line Items - - - - "Electrical" wiring from Nearest Suitable Fixture (in Feet) -- Quantity 10 Feet Per Sign. B. Please include cost for material and labor Installation in DR.A1 and DR.B1 Line Items - - - - Quantity 300 Feet Per Sign of Data Cable for EACH MONITOR.
2	DR. A1 sign-how far does this type of sign suspend from the ceiling	The intent is to suspend these 2 signs 12 feet below the ceiling.
3	DR.B1 sign-Please explain how do you want us to install new sign since the existing sign face is embedded to the horizontal wall structure. And please confirm that new sign will not be embedded like existing sign.	The intent is to flush mount these 2 signs on the existing surface - These signs are not intended to be embedded.
4	ID.B3 sign-please show exact sign location and mounting information on Far-out ceiling is 115" from the floor. And provide information on how far the sign needs to come down. Or if it is a side mount, how far the sign needs to stick out.	The intent is to suspend mount these 37 signs from the Far Out ceiling which measures 115" above the floor so the bottom of the sign is same elevation as the bottom of the lower furred out ceiling. These signs are not intended to be side mounted.
5	For sign type DR.A1, are there monitors on both sides of the sign?	Sign DR.A1 monitors are only on 1 side of the signs. Please also include cost for the supply of 4 monitors total (2 each sign) for Sign Line Item DR.A1 plus material supplies and labor to mount the monitors in DR.A1. Sign DR.B1 monitors are only on 1 side of the signs. Please also include cost for the supply of 2 monitors total (1 each sign) for Sign Line Item DR.B1 plus material supplies and labor to mount the monitors in DR.B1.
6		
7		