

Addendum #1:

This addendum is meant to clarify questions regarding “IT Data Cabling 2026”

**Where in the building is the old cabling that needs to be removed?**

In the same areas and the new cabling to be installed. Many offices have an excess of old cabling installed. We want the new cabling ran and the old cabling in the offices removed.

**What color is the old cabling?**

Various. Mostly blue, white, and some gray. Green was intentionally selected as the new color so that it was easy to identify cabling that should be in place.

**Is there a high likelihood of accidentally cutting something important?**

The likelihood is lower in these areas. The contractor assumes the risk. But the cabling to be removed is either active for desktops/phones and similar endpoint devices and will be replaced by new green cable. Or the cabling to be removed is terminated in a wall plate and unused.

**Is the existing cabling heavily zip tied or Velcro-ed in the ceiling?**

Most of it appears to be laying on ceiling tiles and in other loose configurations.

**There's a lot of discussion in the bid package about fiber but there does not seem to be any fiber worked outlined. Is there fiber work in this bid package?**

No. The airport attached our full division 27 specification which outlines how to use both copper and fiber in our building. However, there is no fiber in the scope of work for this project.